



INTERMEDIATE ROCK STOCKPILE

TYPE 2.02 GENERAL AQUIFER PROTECTION PERMIT

Notice of Intent and Supplemental Information

Submitted To: Resolution Copper Mining LLC

102 Magma Heights Superior, Arizona 85273

Submitted By: Golder Associates Inc.

4730 N. Oracle Road, Suite 210 Tucson, AZ 85705 USA

Distribution:

3 Copies - ADEQ 1 Copies - RCML

2 Copies – Golder Associates Inc.

December 1, 2010

103-92570

A world of capabilities delivered locally





Table of Contents

1.0	NOTICE OF INTENT TO DISCHARGE FOR A TYPE 2 GENERAL PERMIT	1
2.0	NOTICE OF INTENT SUPPLEMENT FOR TYPE 2.02 GENERAL APP FOR INTERMEDIATE STOCKPILES AT MINING SITES	
2.1	Narrative Description of the Intermediate Rock Stockpile	6
2.2	Design, Construction, and Operation to Not Impound Water	7
2.3	Quarterly Inspections	8
2.4	Disposition of Runoff	8
2.5	Maintenance of Engineered Features	8
2.6	Restriction of Hazardous Substances	8
3.0	REFERENCES	9

i

List of Tables

Table 1-1 Existing Environmental Permits for the Superior Mine

Table 2-1 Approximate Loading and Removal Rates

List of Figures

Figure 1-1 Vicinity Map

List of Appendices

Appendix A Design Drawings for the Intermediate Rock Stockpile Appendix B Inspection Form for the Intermediate Rock Stockpile





1.0 NOTICE OF INTENT TO DISCHARGE FOR A TYPE 2 GENERAL PERMIT



ARIZONA DEPARTMENT OF ENVIRONMENTAL QUALITY

Water Permits Section
1110 West Washington Street, MC 5415–B3 • Phoenix, Arizona 85007
(602) 771-4428 • www.azdeg.gov

1

Instructions: Every person who applies for a Type 2 general permit, as provided by Arizona Administrative Code (A.A.C.) Title18, Chapter 9, Article 3, must file a Notice of Intent to Discharge (NOI) required by A.A.C. R18-9-A301(B). In addition to this form, applicants must complete the appropriate NOI Supplemental Form. A separate NOI form and NOI Supplemental form must be completed for each discharging facility (i.e., unit, discharge point) intended to be covered under a general permit. A person intending to operate under a general permit must comply with all the provisions of the general permit and other applicable requirements of statute and rule.

- 1. Type 2 General Permits: Requires notification to the agency of activities to be conducted. Persons must: 1) Meet the requirements of Article 3, Part A and the specific terms of the applicable Type 3 General Permit; 2) File the appropriate NOI forms and supplemental information; 3) Pay applicable general permit review fees. Review fees, which are flat rate fees specified in A.A.C.R18-14-102(C), are NONREFUNDABLE; 4) Satisfy any deficiency requests from the Department; and 5) Receive a written Verification of General Permit Conformance from the Department.
- 2. Type 2 General Permit Notification (check the applicable box):
 - □ 2.01 Dry Wells that Drain Areas Where Hazardous Substances are Used, Stored, Loaded, or Treated

 - □ 2.03 Hydrologic Tracer Studies
 - ☐ 2.04 Dry Wells that Drain Areas Where Motor Fuels are Used, Stored, or Loaded
 - ☐ 2.05 Capacity, Management, Operation, and Maintenance of a Sewage Collection System
 - ☐ 2.06 Fish Hatchery Discharge to a Perennial surface Water
- **3. Applicant:** Resolution Copper Mining Limited (RCML)

Address: 102 Magma Heights PO Box 1944 Superior, Arizona 85273

Phone No.: 520/689-9374 Fax No.: 520/689-9304





4. Contact Person for Facility Operations: Mr. Jonathan C. Cherry, President

Address: Resolution Copper Mining Limited 102 Magma Heights P.O. Box 1944 Superior, Arizona 85273

Phone No.: 520/689-9374 Fax No.: 520/689-9304

5. Name of Owner/Operator responsible for ensuring compliance with this permit if different from No. 3, above:

2

Same as No. 3.

Specify a name, number or other identifier that can be used as a permanent reference to the discharging facility proposed to be covered under this General Permit:

Intermediate Rock Stockpile, West Plant Site

- **7. Location** of the discharging facility proposed to be covered under this General Permit(see Figure 1-1, Vicinity Map):
 - a. County: Pinal County, AZ
 - b. Nearest Community: Superior, AZ
 - c. Legal Description (please reference the property deed. May be by Township, Range, Section; parcel numbers; metes and bounds; subdivision identifiers, etc. Attach separate page if lengthy):

Facility Name	Facility Location				
Intermediate Rock Stockpile	SW1/4 of NE1/4 or NW1/4 of Sec 35 T1S R12E				

Latitude/ Longitude:

Facility Name	Facility Location				
Intermediate Rock Stockpile	LAT 33° 36' 16.1764" LONG 111° 27' 33.6415"				

- **8. Expected dates of discharge:** Date discharges are expected to begin: November 2011. Date discharges are anticipated to cease: December 2019 (i.e., the year closure is complete).
- **9. Existing Environmental Permits:** List all types of state or federal environmental permits already held by the applicant or owner at this location or that are needed for the location: (Attach additional pages if necessary)



Table 1-1 Existing Environmental Permits for the Superior Mine

Type of Permit	Permit Number	Expiration Date	Description
Notice of Disposal		Property Transfer	Filed January 9, 1985
National Pollutant Discharge Elimination System	AZ0020389	Pending	Release of stormwater at Outfall 001 and Treated Effluent at Outfall 002 (renewal application under process)
	59-524492	September 20, 2009	Withdrawal of groundwater not to exceed 5,000 acre/feet/year.
Groundwater Withdrawal Permit	58-130703	August 18, 2005	Withdrawal of groundwater not to exceed 315 acre/feet/year.
	58-117402	June 12, 2011	Withdrawal of groundwater not to exceed 1,490 acre/feet/year.
Wastewater Certificates	WW012411		Wastewater treatment operations Grade 1 Certification
Hazardous Waste / RCRA Identification Number	AZD001886654	Facility Life	United States Environmental Protection Agency (USEPA) Hazardous Waste Identification Number for Annual Reporting
Air Quality Control Permit (Pinal County)	B30820.R3	November 16, 2009	Issued by Pinal County Air Quality Control District
USEPA Stormwater	AZR05A799 Current # AZR05B240	October 2005	No. 9 Shaft (East Plant Site)
Multi-sector General Permits	AZR05A800 Current # AZR05B241	October 2005	West Plant Site
Potable Groundwater(ADEQ Drinking Water Division)	roundwater(ADEQ Drinking Water		No record of renewal can be found
Individual Aquifer Protection Permit	15877.01	Life of Facility	Landfill APP, Nonmunicipal solid waste
Area-wide Aquifer Protection Permit			Discharging Facilities at the West Plant Site
General Aquifer Protection Permit	LTF No. 39202 Inventory No. 105727	February 8, 2011	Type 3.02 General APP for North and South Sludge Storage Impoundments

3

Decer	mber 2010	4	103-92570
10. Certification of Compliance	e. To be completed by the app	olicant.	
I, <u>Jonathan C. Cherry</u> , certify that supervision and all information is, that the facility described in this for the provisions of Article 3 of the am aware that there are significant as well as the possibility of fine an	to the best of my knowled orm is or will be constructed Aquifer Protection Permit r nt penalties for submitting	ge, true, acci d, designed, a rules as they false informa	urate and complete. I also certify and operated in accordance with pertain to this General Permit.

Date

Golder	
Associates	ì

Signature



2.0 NOTICE OF INTENT SUPPLEMENT FOR TYPE 2.02 GENERAL APP FOR INTERMEDIATE STOCKPILES AT MINING SITES



ARIZONA DEPARTMENT OF ENVIRONMENTAL QUALITY

Water Permits Section
1110 West Washington Street, MC 5415–B3 • Phoenix, Arizona 85007
(602) 771-4428 • www.azdeq.gov

This General Permit allows for intermediate stockpiles at mining sites not qualifying as inert under A.R.S. § 49-201(19).

Note: Please ensure that the narrative, design drawings, and any supplemental information provided is comprehensive and adequate to demonstrate conformance with A.A.C. R18-9-D302.

- 1. Provide a **narrative description** of the stockpile addressed under this permit. Specify the expected dates of operation, rate and volume of material to be stockpiled. Include the nature of the material, proposed location, size of footprint, maximum height, and overall slope angle of the intermediate stockpile. See Section 2.1.
- 2. Have you attached the construction and operation specifications to demonstrate:

⊠ Yes	a. The stockpile is designed, constructed, and operated not to impound water. See Section 2.2.
⊠ Yes	b. Inspections will be performed at least quarterly to ensure the design and performance, with any necessary repairs to be made as soon as possible. See Section 2.3.
⊠ Yes	c. All stormwater runoff contacting the pile will be directed to a mine pit or other facility permitted under the Aquifer Protection Program. See Section 2.4.
⊠ Yes	d. All engineered features designed to aid compliance with this permit will be adequately maintained. See Section 2.5.
⊠ Yes	e. No hazardous substances will be added to the stockpile. See Section 2.6.





Resolution Copper Mining LLC (RCML) intends to construct an Intermediate Rock Stockpile for the purpose of staging ore-grade (non-inert) development rock from the advancement of shafts and underground exploration activities. This ore-grade development rock will be generated at the East Plant Site and conveyed to the West Plant Site via the Neversweat Tunnel that connects the two areas of RCML's contiguous property. The ore-grade development rock will be staged in an engineered facility at the West Plant Site until it is processed in the first years of operation of RCML's new mill.

The Intermediate Rock Stockpile will be located at RCML's West Plant Site, immediately north of the closed Tailings Pond 5 and east of the inactive Tailings Ponds 6/7. At full capacity, the footprint of the stockpile will be approximately 6 acres and the volume will be approximately 498,000 cubic yards (702,000 metric tons [tonnes]). The maximum height will be approximately 100 feet as measured from the downhill toe of the stockpile and approximately 50 feet as measured from the uphill toe of the stockpile. The slope angles will range from 1.5H:1V to 3H:1V (horizontal:vertical).

Design drawings for the Intermediate Rock Stockpile are contained in Appendix A. The life cycle for the Intermediate Rock Stockpile will consist of four phases:

- Site excavation (Drawings 2 and 3). Approximately 255,000 cubic yards of Gila Conglomerate will be excavated to create a surface for the stockpile, as well as to generate cover material for closure of historic facilities at the West Plant Site. Only a portion of the excavated surface will be used for the stockpile, however.
- Site preparation (Drawings 4 and 5). This phase will consist of three activities:
 - Two low areas within the footprint of the stockpile will be backfilled with low permeability material to prevent ponding of runoff and/or seepage.
 - Approximately 1,200 linear feet of vee ditch and swale will be used to control runoff from the north side of the stockpile. Approximately 1,400 linear feet of runoff control berm and channel will be constructed to control runoff from west and south sides of the stockpile. A culvert to direct the runoff under a road and then to Tailings Pond 6/7 will also be installed.
 - A third low area uphill from the footprint of the stockpile will be backfilled with compacted common fill to direct potential run-on around the facility. A small existing culvert will be removed and overflow from an existing water tank will be redirected.
- Operation (Drawings 6 and 7). Approximately 498,000 cubic yards (702,000 tonnes) of development rock will be placed within the run-on and runoff controls, and then removed as the material is later processed in RCML's new mill.
- Closure. The ore-grade rock will be removed to the extent practical and the area will be regraded to prevent ponding. The runoff control berm will be removed. RCML will submit a narrative description of closure to ADEQ within 30 days after closure.

Site excavation is expected to begin in January 2011 with site preparation in the third quarter of 2011 and operation beginning in November 2011. The stockpile will receive material for approximately four years at





the approximate rates shown in Table 2-1 and then be inactive for approximately one year while the new mill is being completed. RCML may then take up to two years to run the material through its new mill. The expected date for cessation of operation is December 2018 with closure to occur in 2019.

7

Table 2-1: Approximate Loading and Removal Rate

	Date	Approxima Loaded Remov	l (+) or	Approximate Cumulative Volume		
	Date	Metric Tonnes	Cubic Yards	Metric Tonnes	Cubic Yards	
Jan-Oct 2011	Excavation / site preparation	0	0	0	0	
Nov-Dec 2011	First year of operation (partial)	+17,000	+12,000	17,000	12,000	
2012	Second year of operation	+81,000	+58,000	98,000	70,000	
2013	Third year of operation	+127,000	+90,000	225,000	160,000	
2014	Fourth year of operation	+263,000	+187,000	488,000	346,000	
2015	Fifth year of operation	+214,000	+152,000	702,000	498,000	
2016	Sixth year of operation	0	0	702,000	498,000	
2017	Seventh year of operation	-351,000	-249,000	351,000	249,000	
2018	Eighth year of operation	-351,000	-249,000	0	0	
2019	Closure	0	0	0	0	

The material to be stockpiled was characterized using drill core (Geochimica, 2008) with the characterization approved by ADEQ in 2009 (ADEQ, 2007). According to Geochimica:

"Geochemical reactivity that could adversely affect water quality in rocks to be mined during sinking of Shaft No. 10 is limited to rocks below 1633 meters below ground surface (m bgs) (5,360 feet below ground surface). At and above 1633 m bgs, there is no discernible risk of acid generation, leachable metals (by Method 1312) are not a risk, and total metal concentrations are very low. Below 1633 m bgs, sulfide concentrations are elevated (> 1% weight), there are elevated total metals preset, and metals and some metalloids are leachable under synthetic precipitation testing".

2.2 Design, Construction, and Operation to Not Impound Water

Golder designed the Intermediate Rock Stockpile to not impound water, as shown on the drawing set in Appendix A (particularly Drawings 5, 6, and 7). The top surface, access road, access ramp and outslopes will be graded to prevent ponding. Potential run-on from the northeast will be directed to the southeast around the stockpile using an existing road, thence to the channels on the closed Tailings Pond 5. Runoff from the north outslope of the stockpile will be collected in a vee ditch formed by the intersection of the stockpile toe and the existing hillside. A combination hump and swale will direct runoff from the access ramp and access road to the vee ditch. The vee ditch will report to the berm and channel that collect runoff from the south and west outslopes of the stockpile. The runoff control berm and channel will direct flow to a culvert at the west end of the stockpile, which in turn will direct runoff to the inactive Tailings Pond 6/7. The vee ditch, swales, channel and culvert are designed with continuous downhill grades so as





8

to not impound water. The engineered features for runoff control are designed for the 100-year, 24-hour event.

Under the current topographical configuration, stormwater from the planned stockpile footprint, as well as from uphill of the footprint, reports to the closure channels on Tailings Pond 5, and thence to Tailings Pond 6/7. Under the planned stockpile configuration, potential run-on will report to Tailings Pond 5 and thence to Tailings Pond 6/7; runoff will report to Tailings Pond 6/7. Therefore, the end destination of the stormwater will not change from the current to the planned configurations.

RCML will construct and operate the stockpile to not impound water. The top surface will be routinely graded to not pond water. The design grades in the vee ditch, swales, channel and culvert will be maintained so as to allow continuous flow and not impound water. The inspections described in Section 2.3 will ensure that water is not inadvertently impounded.

2.3 Quarterly Inspections

RCML will visually inspect the facility on at least a quarterly basis, as well as after significant precipitation events. The run-on and runoff controls will be visually inspected for erosion, sedimentation, excessive vegetation, evidence of overtopping and similar conditions that might affect performance. The outslopes of the stockpile will be visually inspected for evidence of potential mass failure (e.g., cracking, sloughing, slumping). RCML will document the inspections using the form in Appendix B.

2.4 Disposition of Runoff

The runoff from the stockpile will be routed to the inactive Tailings Pond 6/7. Tailings Pond 6/7 is permitted for storage of impacted runoff from the West Plant Site under Area-wide APP No. P-101703.

2.5 Maintenance of Engineered Features

RCML will maintain the engineered features in a timely manner as indicated by the quarterly inspections described in Section 2.3. The engineered features consist of the run-on controls (i.e., roads and safety berms) and the runoff controls (i.e., berm, channel, culvert, vee ditch and humps/swales).

2.6 Restriction of Hazardous Substances

Only development rock will be added to the stockpile. RCML will not add hazardous substances to the stockpile.



3.0 REFERENCES


Arizona Department of Environmental Quality, 2007. Technical Memorandum re: Draft Inertness Demonstration Technical Review, Resolution Copper Mining LLC Mine Development Rock, Task Assignment No. EV06-0157, ADEQ Contract No. EV06-0060, Inventory No. 101703, Project LTF 36954, and Site Code 502878-00. March 13, 2007.

9

Geochimica, 2007. Geochemical Characterization of Development Rock for Proposed Shaft No. 10, Resolution Project: ADEQ Tier 1 Results and Inertness Analysis. Prepared for Resolution Copper Mining LLC. January 26, 2007.




FIGURE 1.1 VICINITY MAP



APPENDIX A
DESIGN DRAWINGS FOR INTERMEDIATE ROCK STOCKPILE

INTERMEDIATE ROCK STOCKPILE WEST PLANT SITE, SUPERIOR MINE, SUPERIOR, ARIZONA DECEMBER 2010



LIST OF DRAWINGS

- **EXCAVATION PLAN**
- **EXCAVATION CROSS-SECTIONS**
- SITE PREPARATION PLAN
- SITE PREPARATION CROSS-SECTIONS
- STOCKPILE PLAN
- STOCKPILE CROSS-SECTIONS
- DETAILS

SPECIFICATIONS

- LOW PERMEABILITY FILL SHALL CONSIST OF ONSITE SOIL MATERIALS FROM A SOURCE APPROVED BY THE ROML REPRESENTATIVE. THE MATERIALS SHALL CONSIST OF SILTY SANDS OR SANDY LEAN CLAYS WITH GREATER THAN 40 PERCENT PASSING THE #200 SIEVE. TH
 LOW PERMEABILITY MATERIAL SHALL BE PLACED IN TWO (2) FOOT LIFTS AND COMPACTED TO 95 PERCENT OF STANDARD PROCTOR DENSITY AT OPTIMUM WATER CONTENT (PLUS OR MINUS 2 PERCENT).
- STRUCTURAL FILL COVER SHALL CONSIST OF ONSITE SOIL MATERIALS FROM A SOURCE APPROVED BY THE RCML REPRESENTATIVE. THE MATERIALS SHALL CONSIST OF WELL-TO-POORLY GRADED SAND WITH SILT WITH LESS THAN 15 PERCENT PASSING THE #200 SIEVE. STRUCTURAL FILL SHALL BE PLACED IN TWO (2) FOOT LIFTS AND COMPACTED TO 95 PERCENT OF STANDARD PROCTOR DENSITY AT OPTIMUM WATER CONTENT (PLUS OR MINUS 2 PERCENT).
- COMPACTED COMMON FILL SHALL CONSIST OF CLEAN SOIL MATERIAL EXCAVATED FROM A SOURCE APPROVED BY THE RCML REPRESENTATIVE WITH A MAXIMUM PARTICLE SIZE OF TWELVE (12) INCHES IN DIAMETER. ANY MATERIAL GREATER THAN THE ALLOWABLE PARTICLE SIZE SHALL BE BROKEN DOWN OR REMOVED. COMPACTED COMMON FILL SHALL BE PLACED IN TWO (2) FT LIFTS AND COMPACTED BY TRACKING IN WITH EQUIPMENT WITH AT LEAST THREE (3) PASSES.
- CORRUGATED METAL PIPE (CMP) SHALL BE BITUMINOUS COATED AND FITTINGS SHALL CONFORM TO ASTM A742, A760, A761, A762, A849, A875 AND A929.
- COARSE ROCK COVER SHALL CONSIST OF ONSITE ROCK MATERIALS FROM A SOURCE APPROVED BY THE RCML REPRESENTATIVE. THE MATERIALS SHALL CONSIST OF NON-MINERALIZED -3 INCH ROCK.

GENERAL NOTES

- 1.) TOPOGRAPHIC INFORMATION WAS DEVELOPED BY COOPER AFRIAL SURVEYS CO. JULY 18, 2008. TP-5 AS-BUILT CONTOURS AND EXISTING GROUND
 COUNTOURS PROVIDED BY RCML. ACTUAL GROUND SURFACE ELEVATIONS IN THE PROJECT CAN BE EXPECTED TO VARY PLUS OR MINUS ONE (1) FOOT FROM THOSE INDICATED ON THE DRAWINGS. ACTUAL GROUND SURFACE SHOULD BE VERIFIED BY TOPOGRAPHIC SURVEY BY CONTRACTOR AS NEEDED (AS DETERMINED BY CONTRACTOR) PRIOR TO CONSTRUCTION.
- CONTRACTOR IS RESPONSIBLE FOR APPROPRIATE BLUESTAKE PROCEDURES PRIOR TO EARTHWORK ACTIVITIES. IF AN OVERHEAD, SURFACE, OR SUBSURFACE UTILITY IS ENCOUNTERED, WORK IN THAT AREA WILL BE STOPPED AND THE ROML REPRESENTATIVE WILL BE NOTIFIED IMMEDIATELY. WORK IN THAT AREA WILL NOT RESUME UNTIL DIRECTED BY THE ROML
- THE CONTRACTOR IS RESPONSIBLE FOR THE CONSTRUCTION PROCESS AND THE SAFETY OF THE WORKERS. THIS INCLUDES BUT IS NOT LIMITED TO, THE CONSTRUCTION SEQUENCE, EXCAVATION ACCESS, AND BARRIERS. IT ALSO INCLUDES LIFTING OF MATERIALS AND EQUIPMENT INTO AND OUT OF EXCAVATIONS, TEMPORARY SHORING OF EXCAVATIONS, STABILITY OF ALL TEMPORARY CUT SLOPES ETC.
- CONTRACTOR IS RESPONSIBLE FOR SLOPING EXCAVATIONS TO MAINTAIN SAFE WORKING CONDITIONS IN ACCORDANCE WITH APPLICABLE STANDARDS

VISION DATE

DRAWN BY

TEMPORARY EROSION CONTROL SYSTEMS ARE TO BE PLACED AS FIELD DETERMINED BY THE RCML REPRESENTATIVE TO PROTECT EROSION PRONE

- THE CONTRACTOR IS RESPONSIBLE FOR SALVAGE OF CACTLOR OTHER PLANTS
- THE CONTRACTOR IS RESPONSIBLE FOR DUST CONTROL. AS DIRECTED BY THE



HECKER

Resolution Copper Mining SUPERIOR MINE, SUPERIOR, ARIZONA WEST PLANT SITE

ISSUED FOR PERMITTING ISSUED FOR PERMITTING 11/12/10 ANV WK REFERENCE DRAWING TITLE THIS DRAWING IS NOT VALID UNLESS BY DES



THIS DRAWING PRODUCED BY



HIS DRAWING MAY BE REDUCED FROM ORIGINAL SIZE, DO NOT SCALE his drawing is produced electronically and is only valid for construct f it contains the seal and original signature of an authorized

OCATION

AREA

SUB-AREA TITLE TITLE SHEET GOLDER FILE No

TP-5 AND TP-6/7

ROJECT MANAGER NGINEERING MANAGER ACKAGE MANAGER CIVIL ENGINEER TRUCTURAL ENGINEER MECHANICAL ENGINEER ELECTRICAL ENGINEER STRUMENTATION ENGINEE

EFRIGERATION ENGINEER

VENTILATION ENGINEER

PING ENGINEER

ECTION LEADER

RESOLUTION COPPER

MINING, LLC. ROJECT MANAGER

CONSTRUCTION MANAGER

SAFETY MANAGER

PCM MANAGER

ENGINEERING MANAGER

SITE ENGINEER (MECHANICAL & ELECTRICAL)


SITE ENGINEER (MINING)


GEOTECHNICAL ENGINEER


NVIRONMENTAL ENGINEER


APPROVED FOR GOLDER


PACKAGE MANAGER




















RUNOFF CHANNEL AND CONTROL BERM DETAIL 8




RUNOFF CONTROL CULVERT DETAIL




RUNOFF CONTROL HUMP DETAIL



FILL AREAS #1 AND #2



RUNOFF CONTROL CULVERT SECTION



RUNOFF CONTROL VEE DITCH DETAIL

DRAWN BY:

ANV



R MININ

CHECKER DESIGNER

APPROVED FOR RESOLUTION COPPER MINING, LLC. PROJECT MANAGER

CONSTRUCTION MANAGER

SAFETY MANAGER

EPCM MANAGER

ENGINEERING MANAGER

SITE ENGINEER (MECHANICAL & ELECTRICAL)

SITE ENGINEER (MINING)

GEOTECHNICAL ENGINEER

ENVIRONMENTAL ENGINEER

APPROVED FOR GOLDER

PACKAGE MANAGER

PROJECT MANAGER

ENGINEERING MANAGER

PACKAGE MANAGER

STRUCTURAL ENGINEER

MECHANICAL ENGINEER

ELECTRICAL ENGINEER

INSTRUMENTATION ENGINEER

REFRIGERATION ENGINEER

VENTILATION ENGINEER

PIPING ENGINEER

SECTION LEADER

CIVIL ENGINEER

B ₹₹									THIS DRAWING PRODUCED BY
å <u> </u>									
gwb.									
708006									Caldan
88 8			A	ISSUED FOR PERMITTING	12/01/10	ANV	wĸ	KRJ	Golder
CODE PLINE No:			A	ISSUED FOR PERMITTING	11/12/10	ANV	wĸ	KRJ	Associates
WBS DISCI DWG	REF DWG NO	REFERENCE DRAWING TITLE	REV	DESCRIPTION THIS DRAWING IS NOT VALID UNLESS THE LAST REVISION IS HAND SIGNED	DATE	BY	DES	PROJ MGR	

GHATURE RIGINAL DATE EVISION DATE

DATE: 11/03/10

Resolution Copper Mining

THIS DRAWING MAY BE REDUCED FROM ORIGINAL SIZE, DO NOT SCALE
This drawing is produced electronically and is only valid for construction
if it contains the seal and original signature of an authorized

Resolution Copper Mining CLIENT PROJECT LOCATION AREA SUB-AREA TITLE DETAILS

SUPERIOR MINE, SUPERIOR, ARIZONA WEST PLANT SITE TP-5 AND TP-6/7


GOLDER FILE No 10392570B008 8 B

APPENDIX B INSPECTION FORM FOR THE INTERMEDIATE ROCK STOCKPILE

December 2010 103-92570

INTERMEDIATE ROCK STOCKPILE MONITORING Type 2.02 General Aquifer Protection Permit West Plant Site, Superior Mine

					•		
					Quarterly Monitoring:		Date:
					Significant Event:		
1 Top Surface							
Facility	Ponding Water	is is		Correctiv	ve Actions Required		Corrective Actions Completed
	Por	Other					
Top Surface							
2 Slope Stability of Outslopes/Embank	ments						
		iing	ø				
Facility	Visible Cracks	Sloughing	Slumps		Corrective Actions Required		Corrective Actions Completed
North	> 0	S	S				
South							
West		<u> </u>		<u> </u>			
3 Runoff Controls							
	1	I					
	ies	ping	Obstructions/ Sedimentation				
Facility	Deformities	Overtopping	truct	er	Corrective Actions Requ	ired	Corrective Actions Completed
	Def	Ove	Ops	Other			
North Control Hump							
North Vee Ditch							
East Control Hump							
East Vee Ditch							
South Runoff Channel & Berm							
West Runoff Channel & Berm							
Culvert							
4 Run-on Controls							
		3g	su				
Facility	=	oppir	uctio		Corrective Actions Requ	ired	Corrective Actions Completed
	Erosion	Overtopping	Obstructions	Other			
E '	- 4						
Existing Road Traffic Safety Berm							
Opening to TP 5 Channels							
Opening to 11'5 Channels							



At Golder Associates we strive to be the most respected global group of companies specializing in ground engineering and environmental services. Employee owned since our formation in 1960, we have created a unique culture with pride in ownership, resulting in long-term organizational stability. Golder professionals take the time to build an understanding of client needs and of the specific environments in which they operate. We continue to expand our technical capabilities and have experienced steady growth with employees now operating from offices located throughout Africa, Asia, Australasia, Europe, North America and South America.

Africa + 27 11 254 4800
Asia + 852 2562 3658
Australasia + 61 3 8862 3500
Europe + 356 21 42 30 20
North America + 1 800 275 3281
South America + 55 21 3095 9500

solutions@golder.com www.golder.com

Golder Associates Inc. 4730 N. Oracle Road, Suite 210 Tucson, AZ 85705 USA

Tel: (520) 888-8818 Fax: (520) 888-8817

